

Drawing approval subject to valid vendor registration



NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.

ANNEXURE - II (SURGE ARRESTERS)

GUARANTEED TECHNICAL PARTICULARS FOR 30KV 10KA TYPE-SL METAL OXIDE GAPLESS PORCELAIN LIGHTNING ARRESTER

- | | | |
|--|---|---|
| 1. Name of Manufacturer | : | LAMCO INDUSTRIES PRIVATE LIMITED.
H.O & WORKS: SANATHNAGAR-IE, HYD
WORKS: AUTOMOTIVE PARK, TSIIC,
MUPPIREDDYPALLY, T.S, INDIA. |
| 2. Arrester class & type | : | Station Class Metal Oxide
Gapless Lightning Arrester "MORESTER"
Type-SL, MODEL-'STN-DT' |
| 3. Applicable standard | : | IEC 99-4 of 2014 |
| 4. Rated arrester voltage | | KV : 30 |
| 5. Max. con. operating voltage MCOV | | KV : 25.5 |
| 6. Nominal discharge current with
8/20 micro seconds wave | | KA : 10 |
| 7. Long duration discharge Class | | : 2 (STATION LOW) |
| 8. Energy dissipation capability
(cumulative of 3 sequential shorts) | | KJ/kV of Ur : 4 |
| 9. Max. switching current impulse
residual voltage at
i) 1000 A | | KVpeak : 71 |
| 10. Steep Current Impulse at Nominal
Discharge Current | | KVPeak : 101 |
| 11. Max. residual voltage with 8/20 mic. sec.wave
` | | |
| i) 5 KA | | KVpeak : 85 |
| ii) 10 KA | | KVpeak : 90 |
| iii) 20 KA | | KVpeak : 100 |
| 12. Safe fault current | | Karms : 40 @ 0.2Sec |
| 13. Lightning impulse withstand voltage of
arrester housing with 1.2/50 us wave | | KVpeak : 170 |

1). Minimum 300 mm Plinth shall be maintained for Current transformers in the substation during foundation works to ensure safe live to ground clearances as per IE rules.

2). Since the supply of terminal connectors is not in the scope of CT Manufacturer as mentioned in the drawings, the EPC contractors shall be instructed to supply the same in line with the CT requirement and compatibility.

Continued on page...2

::2::

Chief Engineer
Projects

7537535/2023/EEMRT-ENE51

- | | | |
|-----|---|---|
| 14. | One minute power frequency withstand voltage of housing dry-wet | KVrms : 70 |
| 15. | High current short duration impulse withstand level with 4/10 us wave | KApeak : 100 |
| 16. | Repetitive Charge Transfer Rating (Qrs) in coulomb | : $\geq 1.0C$ |
| 17. | Pressure relief class | Class : A (40 KA) |
| 18. | Over-voltage withstand capability (with prior duty) | |
| | a) 10 seconds | KVpeak : 44 |
| | b) 1 second | KVpeak : 46 |
| | c) 0.1 second | KVpeak : 48 |
| 19. | a) Reference voltage | KV : Greater than the rated Arrester voltage at reference current |
| | b) Reference current | mA : 2 |
| 20. | Number of units per phase and Rating of each unit | : 1
KV : 30 |
| 21. | Minimum total creepage distance | mm : 900 |
| 22. | Leakage current | mA : Less than 0.8 |
| 23. | Total weight of arrester | Kgs : 11 $\pm 10\%$ |
| 24. | Overall Height of SA | mm : 480 ± 20 |
| 25. | Maximum distance recommended from equipment to be protected by SA | mtr : 15 |
| 26. | Min. distance between phase and grounded object | mm : 400 |
| 27. | Min. distance between arrester phase legs | mm : 500 |
| 28. | Partial Discharge Level @1.05 cov | : less than 10pC |
| 29. | Cantilever Strength | : 150Kg (Deflection less than 20mm) |

NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.

1) Minimum 300mm plinth shall be maintained for CT/PT/CVT/Isolators in the substation during foundation works to ensure safe live to ground clearances as per IE rules.

2) Since the supply of terminal connectors is not in the scope of manufacturer as mentioned in the drawings, the EPC contractors shall be instructed to supply the same in line with CT/PT/CVT/Isolators requirement and compatibility.

Chief Engineer
Projects

30. Sesmic Acceleration : 0.3g horizontal & vertical
31. Rated voltage of ZnO disc kV : 4.5
- i) No. of ZnO discs in a unit : 7 (for 30kV)
- ii) No. of units/arrester : 1 (30kV)
- iii) Height/Thickness of ZnO disc mm : 32 ±2
- iv) Diameter of ZnO disc mm : 48 ±2

FOR LAMCO INDUSTRIES PRIVATE LIMITED.



Drawing approval subject to valid vendor registration

(K. ARUN)

SENIOR MANAGER (D&D)



NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.

- 1) Minimum 300mm plinth shall be maintained for CT/PT/CVT/Isolators in the substation during foundation works to ensure safe live to ground clearances as per IE rules.
- 2) Since the supply of terminal connectors is not in the scope of manufacturer as mentioned in the drawings, the EPC contractors shall be instructed to supply the same in line with CT/PT/CVT/Isolators requirement and compatibility.

Chief Engineer
Projects

This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing

NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.




- NOTE :
1. TOTAL CREEPAGE DISTANCE : 900 mm (NOM).
 2. ARRESTER VENT PORT SHOULD BE DIRECTED TOWARDS SAFE DIRECTON.
 3. WEIGHT OF THE ARRESTER : 11±10% Kgs.

Chief Engineer
Projects

Drawing approval subject to valid vendor registration

00	FIRST SUBMISSION	24.05.2023	K.B	K.A	K.A	K.A	
REV.No.	DESCRIPTION	DATE	DRAWN	CHECKED	APPD.	STATUS	
OWNER:		TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED					
CONTRACTOR:		AS APPLICABLE					
PROJECT:		AS APPLICABLE					
L.O.I No.:		AS APPLICABLE					
TITLE:		30kV, 10kA LIGHTNING ARRESTER (MORESTER TYPE-SL,MODEL- STN-DT)					
DRAWING No.		SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.	
MEIL-APT-1239-GDV-S-2500300		A2	NTS	01	01 of 01	00	

This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing




Drawing approval subject to valid vendor registration

NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.

Chief Engineer
Projects

00	FIRST SUBMISSION	24.05.2023	K.B	K.A	K.A	K.A
REV.No.	DESCRIPTION	DATE	DRAWN	ELE. CHECKED	CIVIL	APPD. STATUS
OWNER:		TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED				
CONTRACTOR:		AS APPLICABLE				
PROJECT:		AS APPLICABLE				
L.O.I No.:		AS APPLICABLE				
TITLE:		LINE TERMINAL BRACKET - STN-DT				
DRAWING No.		SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.
MEIL-APT-1239-GDV-S-6220157		A2	NTS	01	01of01	00



DRAWING No.: DRAWINGNO.



Drawing approval subject to valid vendor registration

NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.

Chief Engineer
Projects



- NOTE :
1. MATERIAL : M.S.SHEET.
 2. FINISH : HOT DIP GALVANISED.
 3. WEIGHT : 60 gms.±10%

REV.No.	DESCRIPTION	DATE	DRAWN	CHECKED	APPD.	STATUS
00	FIRST SUBMISSION	24.05.2023	K.B	K.A	K.A	K.A
				ELE.	CIVIL	


OWNER:	TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED					
CONTRACTOR:	AS APPLICABLE					
PROJECT:	AS APPLICABLE					
L.O.I No.:	AS APPLICABLE					
TITLE:	GROUND TERMINAL BRACKET					

DRAWING No.	SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.
MEIL-APT-1239-GDV-S-6220151B	A2	NTS	01	01of01	00

This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing

DRAWING No.: DRAWINGNO.

NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.



Chief Engineer
Projects

Drawing approval subject to valid vendor registration


This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing

S.No.	ITEM	MATERIAL
1.	SP. SUPPORT.	ALUMINUM
2.	RUBBER GASKET.	NEOPRENE ,5mm THICK
3.	SPRING.	SPRING STEEL
4.	SULPHUR CEMENT.	SULPHUR CEMENT
5.	CASTING.	ALUMINIUM (LM-6)
6.	BUSHING.	PORCELAIN
7.	TOP COVER	ALUMINIUM
8.	END COVER PLATE.	ALUMINIUM
9.	COVER PLATE.	M.S (HOT DIP GALVANIZED)
10.	PRESSURE RELIEF DIAPHRAGM.	BRASS
11.	VENT PORT.	ALUMINIUM

REV.No.	DESCRIPTION	DATE	DRAWN	CHECKED	APPD.	STATUS
00	FIRST SUBMISSION	24.05.2023	K.B	K.A	K.A	K.A
OWNER:		TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED				
CONTRACTOR:		AS APPLICABLE				
PROJECT:		AS APPLICABLE				
L.O.I No.:		AS APPLICABLE				
TITLE:		PRESSURE RELIEF AND SEALING ARRANGEMENT OF MORESTER (STN-DT)				
DRAWING No.		SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.
MEIL-APT-1239-GDV-S-4220045		A2	NTS	01	01 of 01	00

This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing

DRAWING No.: DRAWINGNO.



TOP COVER (ALUMINIUM)
 NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.

END CASTING

PORCELAIN BUSHING

ZnO NLR BLOCK

STACK SUPPORT


INSULATING TAPE

Chief Engineer
 Projects

Drawing approval subject to valid vendor registration

00	FIRST SUBMISSION	24.05.2023	K.B	K.A	K.A	K.A		
REV.No.	DESCRIPTION	DATE	DRAWN	ELE. CHECKED	CIVIL	APPD.	STATUS	
OWNER:		TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED						
CONTRACTOR:		AS APPLICABLE						
PROJECT:		AS APPLICABLE						
L.O.I No.:		AS APPLICABLE						
TITLE:		SECTIONAL VIEW OF MORESTER - STN DT						
DRAWING No.		SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.		
MEIL-APT-1239-GDV-S-4420008		A2	NTS	01	01 of 01	00		

This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing



NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.

Chief Engineer
Projects

SHED DETAILS

- NOTE :
1. CREEPAGE DISTANCE FROM A TO B 900mm (MIN).
 2. SURFACES MARKED '△' UNGLAZED, PARALLEL TO EACH OTHER AND PERPENDICULAR TO AXIS.
 3. GLAZE : DARK BROWN.
 4. BORE SHOULD BE STRIGHT AND UNIFORM DIA.
 5. APPLICABLE STANDARD : IEC : 62155.
 6. WEIGHT : 6±10 % Kgs.

Drawing approval subject to valid vendor registration


00	FIRST SUBMISSION	24.05.2023	K.B	K.A	K.A	K.A
REV.No.	DESCRIPTION	DATE	DRAWN	CHECKED	APPD.	STATUS
OWNER:		TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED				
CONTRACTOR:		AS APPLICABLE				
PROJECT:		AS APPLICABLE				
L.O.I No.:		AS APPLICABLE				
TITLE:		PORCELAIN BUSHING 36KV (STN - DT)				
DRAWING No.		SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.
MEIL-APT-1239-GDV-S-6520001		A2	NTS	01	01 of 01	00

DRAWING No.: DRAWINGNO.


NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.

1) Minimum 300mm plinth shall be maintained for CT/PT/CVT/Isolators in the substation during foundation works to ensure safe live to ground clearances as per IE rules.

2) Since the supply of terminal connectors is not in the scope of manufacturer as mentioned in the drawings, the EPC contractors shall be instructed to supply the same in line with CT/PT/CVT/Isolators requirement and compatibility.



Chief Engineer
Projects



SECTION AT 'XX'


TECHNICAL PARAMETERS :

- 1. RATED VOLTAGE (Ur) : 4.5kV (rms)
- 2. MCOV (Uc) : 3.82 kV (rms)
- 3. NOMINADISCHARGE CURRENT (In) : 10KA (PEAK)
- 4. TYPE : STATION LOW DUTY
- 5. REFERENCE STANDARD : IEC 60099-4 ,Ed.3.0,2014-06

This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing

REV.No.	DESCRIPTION	DATE	DRAWN	ELE. CHECKED	CIVIL	APPD.	STATUS
00	FIRST SUBMISSION	02.06.2023	K.B	K.A	K.A	K.A	
OWNER:		TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED					
CONTRACTOR:		AS APPLICABLE					
PROJECT:		AS APPLICABLE					
L.O.I No.:		AS APPLICABLE					
TITLE:		4.5 KV,10KA STATION LOW(SL)ZINC OXIDE BLOCK					
DRAWING No.			SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.
MEIL-APT-1239-GDV-S-6220082-T			A2	NTS	01	01of01	00


This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing



**CHIEF ENGINEER /PROJECTS
APTRANSCO/VISVIJAYAWADA**

00	FIRST SUBMISSION	24.05.2023	K.B	K.A	K.A
REV.No.	DESCRIPTION	DATE	DRAWN	CHECKED	APPD. STATUS
OWNER:	TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED				
CONTRACTOR:	AS APPLICABLE				
PROJECT:	AS APPLICABLE				
L.O.I No.:	AS APPLICABLE				
TITLE:	CHARACTERISTIC CURVES OF ZnO ELEMENTS				
DRAWING No.	SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.
MEIL-APT-1239-GDV-S-8221010	A2	NTS	01	01of01	00

This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing



Drawing approval subject to valid vendor registration

**CHIEF ENGINEER /PROJECTS
APTRANSCO/Vs/VIJAYAWADA**


1) TOV CAPABILITY WITHOUT ENERGY ABSORPTION

REV.No.	DESCRIPTION	DATE	DRAWN	CHECKED	APPD.	STATUS
00	FIRST SUBMISSION	24.05.2023	K.B	K.A	K.A	K.A

OWNER:	TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED				
CONTRACTOR:	AS APPLICABLE				
PROJECT:	AS APPLICABLE				
L.O.I No.:	AS APPLICABLE				
TITLE:	POWER FREQUENCY VOLTAGE Vs TIME CHARACTERISTICS (10 KA)				
DRAWING No.	SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.
MEIL-APT-1239-GDV-S-8221019	A2	NTS	01	01 of 01	00

FOR EPC CONTRACTS ONLY

NOTE : DRAWING APPROVAL SUBJECT TO VALID TYPE TEST REPORTS, TO BE CHECKED DURING ACCEPTANCE TESTS.



Chief Engineer
Projects

Drawing approval subject to valid vendor registration

- NOTE: ±0.05
- 1) MATERIAL : THICKNESS 0.51mm (25 SWG) ALUMINIUM SHEET.
 - 2) PRINTING:
 - a) BORDER LINE AND LETTERS WHITE ON BLACK BACKGROUND.
 - b) LETTER 'L' IN MONOGRAM IS BLACK ON WHITE BACKGROUND.
 - c) RECTANGULAR BLANKS WHITE, LETTERS BLACK.
 - d) LETTERS TO BE ETCHED.

01	FIRST SUBMISSION	02.06.2023	K.B	K.A	K.A	K.A
REV.No.	DESCRIPTION	DATE	DRAWN	CHECKED	APPD.	STATUS
OWNER:	TRANSMISSION CORPORATION OF ANDHRA PRADESH LIMITED					
CONTRACTOR:	AS APPLICABLE					
PROJECT:	AS APPLICABLE					
L.O.I No.:	AS APPLICABLE					
TITLE:	NAME PLATE - STN-DT					
DRAWING No.		SIZE	SCALE	TOTAL SHEETS	SH.No.	REV.
MEIL-APT-1239-GDV-S-8420002		A2	NTS	01	01of01	01

This drawing and design is the property of MEIL and must not be copied or lent without prior permission in writing